

LOCATION MAP
NOT TO SCALE

SITE DATA:

OWNER / DEVELOPER: ASF CONSTRUCTION & EXCAVATION CORP
 PROJECT LOCATION: 37 ROA HOOK ROAD, CORTLAND MANOR, NY, 10567
 EXISTING TOWN ZONING: HC, NONRESIDENTIAL
 PROPOSED USE: HC, NONRESIDENTIAL
 TOWN TAX MAP DATA: Z2-16-4-4
 SITE AREA: 2.375 ACRES (103,443 SF)
 SEWAGE FACILITIES: PRIVATE WELL
 WATER FACILITIES: PRIVATE WELL


ZONING SCHEDULE:

ZONING DISTRICT:	HC, NONRESIDENTIAL				
	DIMENSIONAL REGULATIONS:	REQUIRED	EXISTING	PROVIDED	VARIANCE REQUIRED
MINIMUM SIZE OF LOT:					
MINIMUM LOT AREA:	20,000 SF.	103,443 SF.	103,443 SF.	NONE	
MINIMUM LOT WIDTH:	100 FT.	535 FT.	535 FT.	NONE	
MINIMUM YARD DIMENSIONS:					
PRINCIPAL BUILDING (DWELLING):					
FRONT YARD SETBACK:	30 FT.	54.6 FT.	54.6 FT.	NONE	
REAR YARD SETBACK:	30 FT.	60.1 FT.	60.1 FT.	NONE	
ONE SIDE YARD SETBACK:	30 FT.	191.6 FT.	191.6 FT.	NONE	
SHOP BUILDING:					
FRONT YARD SETBACK:	30 FT.	-----	33.7 FT.	NONE	
REAR YARD SETBACK:	30 FT.	-----	30.0 FT.	NONE	
ONE SIDE YARD SETBACK:	30 FT.	-----	217.6 FT.	NONE	
OPEN STORAGE:					
FRONT YARD SETBACK:	30 FT.	-----	0 FT.	30 FT.	
REAR YARD SETBACK:	30 FT.	-----	84.9 FT.	NONE	
ONE SIDE YARD SETBACK:	30 FT.	-----	0 FT.	30 FT.	
PERCENT OF LOT TO BE OCCUPIED:					
MAXIMUM BUILDING COVERAGE:	20% OF LOT AREA	5% OF LOT AREA*	16% OF LOT AREA	NONE	
MINIMUM LANDSCAPE COVERAGE:	30% OF LOT AREA	32% OF LOT AREA	32% OF LOT AREA	NONE	
MAXIMUM HEIGHT:					
PRINCIPAL BUILDING - FEET:	35 FT.	35 FT. MAX	35 FT. MAX	NONE	
PRINCIPAL BUILDING - STORIES:	2 1/2	-- FT.	1	NONE	
ACCESSORY BUILDING - FEET:	35 FT.	-- FT.	15 FT.	NONE	
ACCESSORY BUILDING - STORIES:	2 1/2	--	2 1/2 MAX	NONE	

*Includes existing structures built off-site to be removed


ZONING REGULATION NOTES:

- No single use, other than a food store, shall occupy more than 4,000 square feet.
- Three- and four-unit dwellings are limited to no more than two bedrooms per unit.
- Existing buildings with more than 20,000 square feet per floor shall not be considered dimensionally nonconforming as per § 307-81 of the Town of Cortland Zoning Code.



LEGEND


- 222 --- EXISTING GRADING
- x 222.8 --- EXISTING SPOT GRADE
- 200 --- PROPOSED GRADING
- --- PROPERTY LINE / RIGHT OF WAY
- --- PROPOSED CURB
- --- PROPOSED STRUCTURE AND DRIVE



NOTE:
 1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON, DATED 12/18/13. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

Site Design Consultants
 Civil Engineers • Land Planners
 251-F Underhill Avenue, Yorktown Heights, NY 10598
 (914) 962-4488, Fax: (914) 962-7386
 www.sitedesignconsultants.com




NO.	DATE	DESCRIPTION
1	8/13/17	1.00 - Information
2	6/1/18	2.00 - Information and Details added
3	7/2/18	3.00 - Final and NYSDEC Comments

SCALE: 1"=20'
 DRAWN BY: MD
 DATE: 10-14-16


SITE PLAN

ANDRE FERNANDES
 37 Roa Hook Road
 Town of Cortland
 Westchester County, NY



PROJECT # 16-29

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488, Fax: (914) 962-7386
www.sitedesignconsultants.com




NO.	DATE	DESCRIPTION
1	8/13/17	FILE INFORMATION
2	6/1/18	LIMITATIONS AND DETAILS ADDED
3	7/2/18	FORM AND NSD&C COMMENTS

SCALE: 1" = 20'
DRAWN BY: MD
DATE: 10-14-16

EXISTING CONDITIONS AND DEMOLITION PLAN

SITE PLAN PREPARED FOR
ANDRE FERNANDES
37 Rox Hook Road
Westchester County, NY
Town of Cortlandt

Sheet 2 of 6




NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON, DATED 12/18/13. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

DISTURBANCE:

	EXISTING		PROPOSED		NET INCREASE	
	DISTURBANCE	IMPERVIOUS	DISTURBANCE	IMPERVIOUS	DISTURBANCE	IMPERVIOUS
WITHIN PROPERTY LINES	0 SF	68,682 SF	58,985 SF	65,015 SF	68,682 SF	-3,667 SF
OUTSIDE PROPERTY LINES	0 SF	26,319 SF	3,575 SF	23,830 SF	3,575 SF	-2,489 SF



PLANTING PLAN
SCALE: 1"=10'-0"

TREE, SHRUB, & HERBACIOUS PLANT SPECIES

PLANT NOTATION	COMMON NAME	SCIENTIFIC NAME	SITE CONDITIONS	QUANTITY	PLANTING SCHEME	PLANTING SEASON
BES	Black-Eyed Susan	<i>Rudbeckia hirta</i>	Sandy/Silty Loam	25	1.0 Foot on Center	May - August
CF	Cone Flower	<i>Echinacea purpurea</i>	Sandy/Silty Loam	40	1.0 Foot on Center	May - August
FD	Flowering Dogwood	<i>Cornus florida</i>	Sandy/Silty Loam	6	7 Feet on Center	April - September
FS	Fragrant Sumac	<i>Rhus aromatica</i>	Sandy/Silty Loam	6	4 Feet on Center	April - September
MS	Meadowsweet	<i>Filipendula ulmaria</i>	Sandy/Silty Loam	25	2.5 Feet on Center	May - August
NB	Nannyberry	<i>Viburnum lentago</i>	Sandy/Silty Loam	40	2.5 Feet on Center	May - August
SG	Switchgrass	<i>Panicum virgatum</i>	Sandy/Silty Loam	30	3 Feet on Center	May - August
SL	Summer Lilac	<i>Buddleia davidii</i>	Sandy/Silty Loam	18	3 Feet on Center	May - August
VC	Virginia Creeper	<i>Parthenocissus quinquefolia</i>	Sandy/Silty Loam	36	2.5 Feet on Center	April - September
WB	Wild Bergamot	<i>Monarda fistulosa</i>	Sandy/Silty Loam	65	1.5 Feet on Center	May - August

VEGETATION PLANTING AREA:

The proposed Vegetation Planting Area will extend east/west along the south edge of the existing lawn area which adjoins the on-site residential structure, for an approximate distance of 95 feet. The width of the area (from the riprap shoreline, into the lawn area) will vary from 12 to 15 feet depending on the configuration of each planted sub-area (denoted by species), as proposed on the Planting Scheme Diagram.

Initial site preparation activities within the planting area will involve the installation of silt fencing along the outer boundaries of the area, followed with the removal of turf grass and excavation of approximately 4 inches of existing topsoil/subsoil. Next, 6 inches of sandy/silty loam soil will be added across the area, the bottom 3 inches of which will first be filled with the existing subsoil before the placement of the remaining 3 inches of the sandy/silty loam; the upper sandy/silty loam soil will be mixed (tilled) with the topsoil removed during initial area preparation. The upper 3 inches of the sandy/silty loam/topsoil will receive a fertilizer application consisting of commercial grade starter fertilizer (a granular, non-burning product), containing 10% nitrogen, 5% available phosphorus, and 4% water soluble potash (10-6-4) if planting occurs in Spring. For Fall, a commercial grade starter fertilizer (also a granular, non-burning product) containing 5% nitrogen, 10% available phosphorus, and 5% water soluble potash (5-10-4) is proposed. An approximate 4 inch hardwood mulch layer will be added above the sandy/silty loam/topsoil mix after plantings are completed.

The table entitled "Tree, Shrub and Herbaceous Plant Species" presents the types of plants selected for the planting area, the planting scheme and number of plants for each of nine (9) proposed species, as well as the planting times for each species, as depicted on the Planting Scheme Diagram. Once the plantings are completed and the hardwood mulch is applied, deer fencing will be installed around the perimeter of the planting area.



Qualified area nurseries will be utilized for purchasing each of the nine plant species, including tree and shrub growers with stock known to successfully become established within the type of climate and site conditions created within the planting area.

The upper soils removed will be temporarily stockpiled for reuse onsite, upgradient of the shoreline within the lawn area while the planting area is prepared; the stockpile will be partially ringed with silt fencing as a sedimentation control. It is anticipated that removal and placement of soil will take from 1 to 2 days, thus, the temporary stockpile of removed soils will promptly utilized within the proposed planting area. A rubber tired back-hoe and a Bobcat excavator will be used for grading to help minimize unnecessary surface impacts.


MITIGATION MONITORING, MAINTENANCE AND REPORTING:

Periodic monitoring activities will be performed to ensure the success of proposed planting area, more specifically, to evaluate the success of each planted species. Once the plantings are complete, periodic monitoring and maintenance will commence. Monitoring will be performed monthly during the first growing season (April through September), followed by quarterly monitoring until 85% vegetative cover is achieved within each proposed planting sub-area. Subsequently, monitoring will continue annually for a three (3) year period or until a minimum of 85 percent (and greater) cover is achieved. Monitoring reports will be provided to the NYSDEC, and the Town of Cortlandt, which will include plant cover density, survival rates, and plant vigor and vitality indicators, as well as photographic documentation and recommended corrective actions, as necessary. Areas void of vegetation will receive additional supplemental plantings, as necessary.

SOILS CLASSIFICATIONS			
TYPE	NAME	DESCRIPTION	HYDROLOGICAL GROUP
us	UDORTHERTS	WET SUBSTRATUM	0



Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 Fax: (914) 962-7386
www.sitedesignconsultants.com



NO.	DATE	REVISIONS/COMMENTS
1	8/13/17	FILE INFORMATION
2	9/1/18	IMPROVEMENTS AND DETAILS ADDED
3	10/15/18	TOWN HALL NYS DEC COMMENTS



SCALE: 1"=20'-0"
DRAWN BY: MD
DATE: 10-14-16


IMPROVEMENT PLAN

ANDRE FERNANDES
37 Roa Hook Road
Town of Cortlandt
Westchester County, NY


NOTE:
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON, DATED 12/18/13. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.






HQ - L- 35:
 LENGTH: 422'
 TURNING RADIUS: 22.9"
 STABILIZER JACKS: 16-18 FT. FULL DEPLOYMENT, 12' SHORT-JACK DEPLOYMENT



E- 252:
 LENGTH: 3111'
 TURNING RADIUS: 23.8"


NOTE:
 1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON, DATED 12/18/13. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



Site Design Consultants
 Civil Engineers • Land Planners
 251-F Underhill Avenue, Yorktown Heights, NY 10598
 (914) 962-4488 • Fax: (914) 962-7386
 www.sitedesignconsultants.com

PROJECT # 16-29
 COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED.



Engineer:
 Joseph C. Fernandez, P.E.
 NYS Lic. No. 44131

Revisions:

No.	Date	Comments
1.	8/03/17	Take Information
2.	6/1/18	Improvements and Details added
3.	7/2/18	Form and NYSDEC Comments

SCALE:
 1" = 20'

DRAWN BY:
 MD

DATE:
 10-14-16







FIRE ACCESS
 PLAN

SITE PLAN
 PREPARED FOR
ANDRE FERNANDES
 37 Rox Hook Road
 Town of Cortlandt


Westchester County, NY


Sheet
 4 of 6

SAFETY
 Before You Dig, Drill or Blast!
 Call 811
 1-800-4-A-DAWG
 Call 811
 1-800-4-A-DAWG
 Call 811
 1-800-4-A-DAWG



© 2018 ANDRE FERNANDES, A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW YORK. RECOVERED FROM THE INTERNET 4/18/2023 PM


Site Design Consultants
 Civil Engineers • Land Planners
 251-F Underhill Avenue, Yorktown Heights, NY 10598
 (914) 962-4488 • Fax: (914) 962-7386
 www.sitedesignconsultants.com


 Engineer: Joseph P. Fernandez, P.E.
 License No. 6451

NO.	DATE	COMMENTS
1.	8/03/17	Final Information
2.	6/1/18	Improvements and Details added
3.	5/15/18	Final and ASB/SLC Comments




SCALE: N/A
 DRAWN BY: MD
 DATE: 5-14-18

PROFILES & DETAILS

ANDRE FERNANDES
 37 Roa Hook Road
 Town of Cortlandt
 Westchester County, NY

SHEET 5 OF 6

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.






GENERAL EROSION CONTROL NOTES:

- Contractor shall be responsible for compliance with all sediment and erosion control practices. The sediment and erosion control practices are to be installed prior to any major soil disturbances, and maintained until permanent protection is established. Road surface flows from the site should be dissipated with tracking pad or appropriate measures during adjacent road shoulder regrading. Contractor is responsible for the installation and maintenance of all soil erosion and sedimentation control devices throughout the course of construction.
- Catch basin inlet protection must be installed and operating at all times until tributary areas have been stabilized. When possible flows should be stabilized before reaching inlet protection structure. Timely maintenance of sediment control structures is the responsibility of the Contractor.
- All structures shall be maintained in good working order at all times. The sediment level in all sediment traps shall be closely monitored and sediment removed promptly when maximum levels are reached or as ordered by the engineer. All sediment control structures shall be inspected on a regular basis, and after each heavy rain to insure proper operation as designed. An inspection schedule shall be set forth prior to the start of construction.
- The locations and the installation times of the sediment capturing standards shall be as specified in these plans, as ordered by the Engineer, and in accordance with the latest edition of the "New York Standards and Specifications for Erosion and Sediment Control" (NYSSESC).
- All topsoil shall be placed in a stabilized stockpile for reuse on the site. All stockpile material required for final grading and stored on site shall be temporarily seeded and mulched within 7 days. Refer to soil stockpile details.
- Any disturbed areas that will be left exposed more than 7 days and not subject to construction traffic, shall immediately receive temporary seeding. Mulch shall be used if the season prevents the establishment of a temporary cover. Disturbed areas shall not be limed and fertilized prior to temporary seeding.
- All disturbed areas within 500 feet of an inhabited dwelling shall be wetted as necessary to provide dust control.
- The contractor shall keep the roadways within the project clear of soil and debris and is responsible for any street cleaning necessary during the course of the project.
- Sediment and erosion control structures shall be removed and the area stabilized when the drainage area has been properly stabilized by permanent measures.
- All sediment and erosion control measures shall be installed in accordance with current edition of NYSSESC.
- All regraded areas must be stabilized appropriately prior to any rock blasting, cutting, and/or filling of soils. Special care should be taken during construction to insure stability during maintenance and integrity of control structures.
- Any slopes graded at 3:1 or greater shall be stabilized with erosion blankets to be staked into place in accordance with the manufacturer's requirements. Erosion blankets may also be required at the discretion of Town officials or Project Engineer. When stabilized blanket is utilized for channel stabilization, place all of the volume of seed mix prior to laying net, or as recommended by the manufacturer.
- To prevent heavy construction equipment and trucks from tracking soil off-site, construct a pervious crushed stone pad. Locate and construct pads as detailed in these plans.
- Contractor is responsible for controlling dust by sprinkling exposed soil areas periodically with water as required. Contractor to supply all equipment and water.
- Contractor shall be responsible for construction inspections as per NYSDEC GP-0-15-002 and Town of Yorktown Code.

TOPSOIL:
Existing topsoil will be removed and stored in piles sufficiently to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYS DOT):

- The pH of the material shall be 5.5 to 7.6.
- The organic content shall not be less than 2% or more than 70%.
- Gradation:

SIEVE SIZE	% PASSING BY WGT.
2 INCH	100
1 INCH	85 TO 100
1/4 INCH	65 TO 100
NO. 200 MESH	20 TO 80



PERMANENT VEGETATIVE COVER:

- Site preparation:
 - Install erosion control measures.
 - Scarify compacted soil areas.
 - Lime as required to pH 6.5.
 - Fertilize with 10-6-4 4 lbs/1,000 S.F.
 - Incorporate amendments into soil with disc harrow.
- Seed mixtures for use on swales and cut and fill areas.

MIXTURE	ALT. A	ALT. B	LBS./ACRE
KENTUCKY BLUE GRASS			20
CREeping RED FESCUE			28
RYE GRASS OR REDTOP			5
CREeping RED FESCUE			20
REDTOP			2
TALL FESCUE/SMOOTH BLOOMGRASS			20
- SEEDING:
 - Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.
 - Apply soil amendments and integrate into soil.
 - Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
 - Stabilize seeded areas in drainage swales.
 - Irrigate to fully saturate soil layer, but not to dislodge planting soil.
 - Seed between April 1st and May 15th or August 15th and October 15th.
 - Seeding may occur May 15th and August 15th if adequate irrigation is provided.

TEMPORARY VEGETATIVE COVER:

SITE PREPARATION:

- Install erosion control measures.
- Scarify areas of compacted soil.
- Fertilize with 10-10-10 at 400/acre.
- Lime as required to pH 6.5.

SEED SPECIES:

MIXTURE	LBS./ACRE
Rapidly germinating annual ryegrass (or approved equivalent)	20
Perennial ryegrass	36
Cereal oats	20

SEEDING:
Same as permanent vegetative cover




CONTRACTOR CERTIFICATION STATEMENT
Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 29, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: _____
Name and Title (please print): _____
Signature of Contractor: _____
Company / Contracting Firm: _____
Name of Company: _____
Address of Company: _____
Telephone Number / Cell Number: _____
Site Information: _____
Address of Site: _____
Today's Date: _____

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 • Fax: (914) 962-7586
www.sitedesignconsultants.com

Professional Engineer
Joseph P. L. P.E.
NYS Lic. No. 6451



MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE	---	INSP	---	INSP	CLEAN/REPLACE	REMOVE
WHEEL CLEANER	---	---	---	---	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:
The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:
Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

DEBRIS AND LITTER REMOVAL:
Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation.

STRUCTURAL REPAIR/REPLACEMENT:
Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

EROSION CONTROL:
Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures.

SEDIMENT REMOVAL:
Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.




CONSTRUCTION SEQUENCE:
Refer to the Plan Set for all plans and details which relate to Construction Sequence.

- A licensed surveyor must define infrastructure locations, limits of disturbance, stormwater basin limits, and grades in the field prior to start of any construction. Limits of disturbance shall be marked with the installation of construction fence or approved equivalent. The extent of all of the stormwater management systems shall be cordoned off to minimize the disturbance on this area.
- Install all perimeter erosion control measures, construction access as shown on the Erosion and Sediment Control Plan and the associated Details. Install silt fencing at the bottom of slopes.
- Strip site and place topsoil in stockpile locations shown on the plan.
- Begin rough grading the site. Contractor to limit exposure of denuded soils by providing temporary stabilization for work areas that will remain undisturbed for over seven (7) days. Excess material shall be stockpiled in the location shown on the plan as grades allow. Material unable to be stockpiled shall be removed from the site.
- Rough grade building and driveway.
- Begin construction of building.
- Begin the excavation and installation of stormwater management system. Protect trenches and open excavations from erosion. Entry into the system shall be blocked off until site has reached final stabilization. Once system has been installed, backfill, seed where necessary, and reinstall measures to cord off the system from disturbance.
- During site construction maintain and re-establish as required erosion control and stabilization measures as required by the site plan and details.
- Excavate to the sub-grade level. Scarify the existing soil to a depth of 12-inches by rototilling or other means acceptable to the Engineer. Install all courses of stone as per the specifications given on the Plan.
- Install base course of Item 4 in all pavement areas. Stabilize all open areas with seed and mulch.
- Construct remainder of building, driveway and parking areas. Install asphalt binder. Once binder course is installed, drainage outlet may be unlocked.
- Grade, place final soil topping and put in place permanent vegetative cover over all disturbed areas, landscape beds, slopes, etc.
- Once site stabilization has taken place (An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements), remove all temporary erosion and sediment controls, unplug the drainage system to allow runoff to enter the stormwater management system.

Winter Stabilization Notes:
If construction activities are expected to extend into or occur during the winter season the contractor shall anticipate proper stabilization and sequencing. Construction shall be sequenced such that wherever possible areas of disturbance that can be completed and permanently stabilized shall be done by applying and establishing permanent vegetative cover before the first frost. Areas subject to temporary disturbance that will not be worked for an extended period of time shall be treated with temporary seed, mulch, and/or erosion blankets.

DETAILS


Scale: N/A
Drawn by: MD
Date: 5-14-18



OWNER / OPERATOR CERTIFICATION
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): _____
Title: _____
Date: _____
Address: _____
Phone: _____
E-mail: _____
Signature: _____

SITE PLAN
PREPARED FOR
ANDRE FERNANDES
37 Roa Hook Road
Town of Cortlandt
Westchester County, NY



CONSTRUCTION SEQUENCE:
Refer to the Plan Set for all plans and details which relate to Construction Sequence.

Sheet 6 of 6