

FIELD SURVEY (LATEST MAP DATED 5/5/2017) BY

Unauthorized alterations or additions to this drawing is a violation of Section 7209 (2) of the New York State

TC MERRITTS LAND SURVEYORS.

Education Law.

AMENDED SITE PLAN PROPOSED BUILDING PREPARED FOR MEENAN OIL CO., LP TOWN OF CORTLANDT WESTCHESTER COUNTY, NY 18, 2017 MAY

Reviewed by the Department of Environmental Services Reviewed by the Department of Technical Services

SCALE IN FEET

Approved by Resolution No. \_\_\_\_\_ of the Planning Board of the Town of Cortlandt, New York on the \_\_\_ day of \_\_\_\_\_, 20\_\_, subject to all requirements and conditions of said Resolution. Any change, erasure, modification of revision in this plat or site development plan, after the above date, shall void this approval. Signed this  $\_\_$  day of  $\_\_$ ,  $20\_$  by

Chairman of the Planning Board

## ZONING COMPLIANCE CHART

26 BAYVIEW ROAD			
SECTION 22.19, BLOCK 1, LOT 4		MAIN BLDG	ELEC. BLDG
DISTRICT M-1A, LIGHT INDUSTRIAL	REQUIRED	PROPOSED	PROPOSED
MINIMUM LOT AREA	20,000 SF	337,141 SF	337,141 SF
MINIMUM LOT WIDTH	100'	>100	>100
	100		
MAXIMUM HEIGHT			
IN FEET	40'	22'	15'
MINIMUM YARD DIMENSIONS			
FRONT	40'	446'	590'
SIDE	20'	27'	145'
REAR	30'	31'	2' *
MAXIMUM BUILDING COVERAGE	35%	2.2%	0.04%
TOTAL BUILDING COVERAGE			2.24%

\* PROPOSED LOCATION REQUIRES REAR YARD VARIANCE FROM ZBA \* ALTERNATE LOCATION DOES NOT REQUIRE REAR YARD VARIANCE

REVISED: MAY 16, 2018

REVISED: MARCH 12, 2018

REVISED: FEBRUARY 16, 2018


REVISED: DECEMBER 12, 2017


REVISED: SEPTEMBER 19, 2017

1. THE EXISTING LIGHTS OPERATION HOURS ARE REGULATED BY THE U.S. COAST GUARD AND ARE ILLUMINATED FROM APPROXIMATELY DUSK TO DAWN. 2. FEMA INFORMATION FROM MAP NUMBER:

36119C0012F EFFECTIVE DATE: 9/28/2007

RALPH G. MASTROMONACO, P.E., P.C. Consulting Engineers 13 Dove Court, Croton-on-Hudson, New York 10520 (914) 271-4762 (914) 271-2820 Fax






TO BE USED WHERE TOPSOIL PRESERVATION IS NECESSARY FOR REGRADING AND VEGETATING DISTURBED AREAS. TOPSOIL IS APPLIED TO SUBSOILS THAT ARE DROUGHTY (HAVING LOW AVAILABLE MOISTURE FOR PLANTS), STONY, SALTY, HAVE LOW PERMEABILITY, OR ARE EXTREMELY ACID. IT IS ALSO USED TO BACKFILL AROUND SHRUB AND TREE TRANSPLANTS. PRESERVATION OF EXISTING TOPSOIL IS BENEFICIAL FOR ALL TYPES OF LAWN OR ORNAMENTAL PLANTINGS

TEMPORARY STOCKPILE STABILIZATION MEASURES INCLUDE VEGETATIVE COVER, MULCH, NON-VEGETATIVE COVER, AND PERIPHERAL SEDIMENT TRAPPING BARRIERS. THE STABILIZATION MEASURE(S) SELECTED SHOULD BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, AND REQUIRED DURATION OF USE.


### INSTALLATION NOTES

- 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2.
- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR COVERED.

SOIL STOCKPILING N.T.S.




LEADER DRAIN CONNECTION N.T.S.



PRECAST CONCRETE SPLASH BLOCK N.T.S.


Unauthorized alterations or additions to this drawing is a violation of Section 7209 (2) of the New York State Education Law.





SILT FENCE AND HAYBALE DETAIL N.T.S.

# SELECT FILL COMPACTED IN 12" LIFTS FINISHED GRADE VARIES DIA. VARIES DRAIN PIPE BEDDING N. T. S.

# Railings shall be 1 1/2" welded Schedule 40 aluminum or galvanized steel pipe. Balusters shall be 1" Schedule 40 pipe of the same alloy with max. 4" opening between balusters. Posts shall be 1 1/2" Schedule 40 pipe of the same alloy. Post spacing shall be a maximum of 6'-0".










PROPOSED WALL MOUNTED LED LIGHT FIXTURE: BEACON "TRANSVERSE SERIES" BY HUBBELL LIGHTING









WALL MOUNTED LED LIGHT FIXTURE N.T.S.

Siltsack is a temporary catch basin filter that removes sediment, trash and debris from entering a catch basin.

1. To install Siltsack in the catch basin, remove the grate and place the sack in the opening. Hold

approximately six inches of the sack outside the frame. This is the area of the lifting straps. Replace


the grate to hold the sack in place.

2. When the restraint cord is no longer visible, Siltsack is full and should be emptied.

3. To remove Siltsack, take two pieces of 1" diameter rebar and place through the lifting loops on each side of the sack to facilitate the lifting of Siltsack.
4. To empty Siltsack, place unit where the contents will be collected. Place the rebar through the lift straps (connected to the bottom of the sack) and lift. This will lift Siltsack from the bottom and empty the contents. Clean out and rinse. Return Siltsack to its original shape and place back in the

5. Siltsack is reusable. Once the construction cycle is complete, remove Siltsack from the basin and

# Silt Sack - Type A



"SILT SACK" SEDIMENT CAPTURE DEVICE FOR EXISTING DRAIN INLETS N.T.S.

REVISED: MARCH 12, 2018 REVISED: FEBRUARY 16, 2018 REVISED: DECEMBER 12, 2017 REVISED: SEPTEMBER 19, 2017

### GENERAL NOTES:

1. THE CONTRACTOR SHALL LOCATE AND VERIFY IN THE FIELD ALL UTILITIES — GAS, WATER, ELECTRICAL BEFORE THE START OF CONSTRUCTION. CONTRACTOR SHALL CALL CODE 753 (FORMERLY CODE 53).

2. ALL PROPERTY DISTURBED IN THE R.O.W. OR ON PRIVATE LANDS, SHALL BE RESTORED TO NEW CONDITIONS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL APPLICATIONS AND PERMITS REQUIRED FOR CONSTRUCTION.
 UNDERGROUND GAS AND ELECTRIC SHALL BE AS REQUIRED BY THE TOWN AND CON EDISON.

- 5. TELEPHONE AND CABLE LINES TO BE UNDERGROUND.
- 6. ALL DRAINAGE PIPE TO BE HDPE UNLESS OTHERWISE NOTED.
  7. ALL GRADED SLOPES SHALL NOT EXCEED 1 VERTICAL ON 2 HORIZONTAL UNLESS OTHERWISE APPROVED BY THE TOWN ENGINEER.
  8. ALL STRUCTURES TO BE PLACED IN PAVED AREAS SHALL BE DESIGNED FOR H-20 LOADING.
- 9. ANY FILL IMPORTED TO THE SITE SHALL BE TESTED AND ALL RESULTS SUBMITTED TO THE TOWN PRIOR TO IMPORTING AND PLACING.10. ALL FOOTINGS SHALL BE A MINIMUM OF 3'-6" BELOW FINISHED GRADE.
- GENERAL EROSION CONTROL NOTES:

  1. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION AND MAINTAINED IN EFFECTIVE CONDITION
- 2. ALL EROSION AND SEDIMENTATION CONTROL MEASURES AND PROCEDURES SHALL COMPLY WITH THE STANDARDS AND SPECIFICATIONS OF THE THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION "EROSION AND SEDIMENT CONTROL GUIDELINES FOR NEW DEVELOPMENT".
- 3. PRIOR TO ANY EXCAVATION, HAY BALES/SILT FENCE SHALL BE INSTALLED AT THE APPROPRIATE LOCATIONS NOTED ON EROSION CONTROL PLAN. HAYBALES/SILT FENCING SHALL BE INSTALLED AS DIRECTED BY THE OWNER'S REPRESENTATIVE IN THE FIELD AND INSTALLED AS PER THE INSTRUCTIONS OF THE MANUFACTURER. ADDITIONAL HAYBALES/SILT FENCE MAY BE PLACED BY THE OWNER'S REPRESENTATIVE IN THE FIELD. HAYBALES/SILT FENCING SHALL BE MAINTAINED IN OPERABLE CONDITION AND SHALL NOT BE REMOVED UNTIL DISTURBED AREAS ARE THOROUGHLY
- 4. IMMEDIATELY TOPSOIL & SEED WITH A MIXTURE OF PERENNIAL RYE GRASS, ANNUAL RYE GRASS AND WINTER RYE AND MULCH WITH 6" OF HAY ALL FINISHED SLOPES AND ALL ROUGH CUT SLOPES TO REMAIN OPEN FOR EXTENDED PERIODS.
- 5. ALL SLOPES CONSTRUCTED WITH FILL MATERIAL AND ALL SLOPES WITH GRADE 3:1 OR STEEPER SHALL BE TOPSOILED, SEEDED, MULCHED AND STABILIZED WITH STAKED TOBACCO NETTING, UNLESS OTHERWISE NOTED
- ALL AREAS OF DISTURBED SOIL SHALL BE STABILIZED. IN ADDITION
  TO ALL SPECIFIED AND LOCATED EROSION CONTROL DEVICES, THE
  CONTRACTOR SHALL TAKE ALL STEPS PRUDENT AND NECESSARY TO
  STABILIZE THE SITE AT ALL TIMES.
- DO NOT STOCKPILE MATERIALS ON STEEP SLOPES, IN DRAINAGE SWALES OR IN WETLAND AREAS. SURROUND ALL STOCKPILE AREAS WITH STAKED HAYBALES OR SILT SCREEN MATERIALS.
- 8. ALL CATCH BASINS ARE TO BE PROTECTED WITH APPROPRIATE FILTERS THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
- 9. HAYBALES SHALL BE USED AT THE TOPS AND TOE OF SLOPES, AS NECESSARY, TO COLLECT SILT AND DIVERT FLOWS. SILT SCREENS WILL BE USED IN AREAS OF UNCONCENTRATED FLOWS TO COLLECT SILT. HAYBALES AND SILT SCREEN ON PLANS MAY BE AUGMENTED IN
- 10. UTILITY LINE EXCAVATED MATERIAL SHALL BE TEMPORARILY STOCKPILED ON HIGH SIDE OF EXCAVATION SO RUNOFF IS DIRECTED AWAY FROM TRENCH. AFTER BACK-FILLING, AREA IS TO BE TOPSOILED, SEEDED AND MULCHED OR PAVED.
- I. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE
- 12. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN THEY REACH APPROXIMATELY ONE—HALF THE HEIGHT OF THE BARRIER. SEDIMENT SHALL BE DISPOSED OF IN A MANNER THAT DOES NOT RESULT IN ADDITIONAL EROSION OR POLLUTION.

RALPH G. MASTROMONACO, P.E., P.C. Consulting Engineers
13 Dove Court, Croton-on-Hudson, New York 10520

(914) 271-4762 (914) 271-2820 Fax

DETAILS/NOTES
PROPOSED BUILDING
PREPARED FOR
MEENAN OIL CO., LP
TOWN OF CORTLANDT
VESTCHESTER COUNTY, NY
MAY 18, 2017